

OFFICE OF ATTORNEY GENERAL
Construction of boundary fencing & development of parking
Bill of Quantities

Sl. no.	Item Description	Unit	Quantity	Rate, Nu./Unit		Amount, Nu.
				In figure	In words	
1	BOUNDARY WALL					
a)	Earthwork in Excavation in foundation trenches or drains including dressing of sides and ramming of bottom, disposal of surplus excavated soil within 50m lead - hard soil.	cu.m	123.15			
b)	Providing and laying 150 mm thick hand packed stone filling or soling with stones.	cu.m	42.27			
c)	Providing and laying in position 75 mm thick plain cement concrete 1:3:6 excluding the cost of centering and shuttering - All work upto plinth level.	cu.m	26.1			
d)	Providing & laying Random Rubble Masonry with hard stone in foundation & plinth in cement mortar 1:3.	cu.m	39.9			
e)	Providing & laying Coursed Rubble Masonry with hard stone hammer-dressed:					
i)	In foundation & plinth in cement mortar 1:3 .	cu.m	38.26			
ii)	In superstructure above plinth, below & including floor 2 level.	cu.m	90.44			

OFFICE OF ATTORNEY GENERAL
Construction of boundary fencing & development of parking
Bill of Quantities

Sl. no.	Item Description	Unit	Quantity	Rate, Nu./Unit		Amount, Nu.
				In figure	In words	
g)	Providing and laying in position plain cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc. upto floor five level, excluding the cost of centering and shuttering in 1:3:6 (1 cement : 3 sand : 6 graded crushed rock 40 mm nominal size).	cu.m	4.32			
h)	Providing & laying cement plaster, finished with floating coat of neat cement in 15mm plaster in C.M 1:3.	Sq.m	189.33			
i)	Providing & fixing Thermo-Mechanically Treated reinforcement bar (Yield Strength 500 MPa) for R.C.C work including cutting, bending, binding and placing in position complete.	kg	3374.97			
j)	Providing & fixing centering and shuttering (formwork), including strutting, propping etc. and removal of formwork - Foundation and plinth etc.					
i)	Foundation and plinth etc.	sq.m	67.2			
ii)	Columns, pillars, post, struts etc.	sq.m	188.8			
	Sub-Total - (1)					

OFFICE OF ATTORNEY GENERAL
Construction of boundary fencing & development of parking
Bill of Quantities

Sl. no.	Item Description	Unit	Quantity	Rate, Nu./Unit		Amount, Nu.
				In figure	In words	
2	PARKING WORKS					
a)	Earthwork in excavation over areas, exceeding 300mm in depth, 1.5 m in width as well as 10 sq.m on plan including disposal of excavated earth in designated locations including loading/unloading, dressing of dump sites.	cu.m	1750.00			
b)	Preparation of sub grade with proper camber by excavating earth to depth equal to pavement thickness, consolidation with roller, disposal of surplus earth up to 50m - All kinds of soil.	cu.m	560.00			
c)	Providing and laying hammer dressed dry stone soling.- 200mm thick.	cu.m	280.00			
d)	Providing and laying in position 200 mm thick plain cement concrete excluding the cost of centering and shuttering - All work upto plinth level in CM 1:3:6 in parking lot.	cu.m	280.00			
	Sub-Total - (2)					
	Grand Total : Subtotal (1)+(2)					

Grand total in words: Ngultrum